



Shingle roofing · Example: Two-story house with front gables

Sample sheet · a real plan set with the address removed

SHINGLES + UNDERLAYMENT

| QTY | UNIT    | ITEM                       | NOTE          |
|-----|---------|----------------------------|---------------|
| 172 | bundles | Architectural shingles     |               |
| 5   | bundles | Starter strip              |               |
| 7   | bundles | Hip + ridge cap            |               |
| 5   |         | Synthetic underlayment     | 10 - sq rolls |
| 10  |         | Ice & water membrane       | 2 - sq rolls  |
| 4   | boxes   | Coil nails, 1¼" ring shank |               |
| 1   | box     | Cap nails, 1"              |               |

METAL, FLASHING + VENTS

| QTY | UNIT | ITEM                 | NOTE  |
|-----|------|----------------------|-------|
| 21  |      | Gutter apron         | 10 ft |
| 37  |      | Drip edge, rakes     | 10 ft |
| 18  |      | Valley metal, 24" W  | 10 ft |
| 329 | pcs  | Step flashing 8×8    |       |
| 18  |      | Counter flashing 10" | 10 ft |
| 4   | ea   | Pipe boots, 2"       |       |
| 1   | ea   | Fan - duct roof jack |       |

---

**Estimate from plans - verify on site before ordering.** Plans don't show pony walls, field changes or site conditions. A site visit is recommended.

Measured off a 3D model built from the plan set. [10minutebids.com](https://10minutebids.com)