



Siding · Example: Two-story house with front gables

Sample sheet · a real plan set with the address removed

SIDING + TRIM

QTY	UNIT	ITEM
662	pcs	Fiber cement lap 8¼" × 12'
49	pcs	Corner boards 5/4 × 4 × 12'
53	pcs	Casing 5/4 × 4 × 12'
77	pcs	Fascia 5/4 × 8 × 12'
47	pcs	Soffit panels 24" × 8'
17	pcs	Drip cap, 10'

WRAP, FLASHING + FASTENERS

QTY	UNIT	ITEM
5	rolls	House wrap, 9' × 125'
5	rolls	Seam tape, 165'
456	pcs	Furring 1×3 × 8', rainscreen
529	ea	Butt-joint flashing
2	boxes	Siding nails, stainless
2	boxes	Trim nails, 8d ring shank
69	tubes	Sealant, 10 oz

Estimate from plans - verify on site before ordering. Plans don't show pony walls, field changes or site conditions. A site visit is recommended.

Measured off a 3D model built from the plan set. 10minutebids.com